JUPITER PRIME
Consulting • Training • Advisory
جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

Electrical and Instrumentation Design Deliverables Training Course

4 – 8 October 2027
Paris

Electrical and Instrumentation Design Deliverables Training Course

Ref: 2709_103413 **Date:** 4 – 8 October 2027 **Location:** Paris **Fees:** 6900 GBP

Electrical and Instrumentation Design Deliverables is a 1-week training course for junior electrical and instrumentation engineers and designers who produce drawings, schedules and calculations for new plant, and it ends with a checked electrical and instrumentation design package for one process unit. Projects now move faster and with leaner engineering teams, so errors in early deliverables travel straight into procurement and construction. Jupiter Prime Training delivers this course on electrical and instrumentation design deliverables.

Why Electrical and Instrumentation Design Deliverables Matter Now

Three pressures shape electrical and instrumentation design today. Engineering contractors and owners compress schedules, so a junior designer may issue a single-line diagram or an instrument datasheet with little senior checking. Digital plant models link drawings, cable schedules and instrument indexes, so one wrong attribute repeats across many documents. And construction and commissioning teams expect deliverables they can build and test from without queries. An organisation whose designers follow consistent sizing methods, naming conventions and checking routines avoids rework, late cable orders and hazardous area nonconformities; one that does not pays for them on site.

Who Gains Most from Electrical and Instrumentation Design Deliverables

- Designers preparing single-line diagrams, layouts and schedules for power distribution
- Engineers calculating cable sizes, voltage drop and lighting levels
- Engineers specifying field instruments and writing datasheets
- Designers drawing loop diagrams, wiring and junction box arrangements
- Engineers matching equipment to hazardous area classification

A contractor design office gains most when several junior designers attend and adopt one checking routine.

Electrical and Instrumentation Design Deliverables Capabilities

Participants turn process data into buildable drawings and schedules.

- Build a single-line diagram with ratings and protection — the lead electrical engineer
- Calculate cable sizes for current, voltage drop and short-circuit withstand — the procurement team ordering cable
- Design lighting and small power layouts for plant rooms and outdoor areas — the facility operator
- Specify field instruments and write datasheets — the instrument vendor
- Apply hazardous area zones to equipment selection — the safety reviewer
- Test deliverables for consistency — the document controller issuing for construction

Key Electrical and Instrumentation Design Deliverables Terms

- Single-line diagram — a simplified drawing of power flow from supply to loads through switchgear and protection.
- Load schedule — a table of every consumer with its rating and demand.
- Voltage drop — the fall in voltage along a loaded cable.
- Instrument index — the master list of instrument tags with service, type and range.
- Loop diagram — a drawing tracing one signal from field device to control system.
- Hazardous area classification — zoning of a plant by the likelihood of a flammable atmosphere.

Electrical and Instrumentation Design Deliverables Day by Day

Day 1: From Process Data to Electrical Loads

- Process Flow and Piping Diagrams — Identifying Electrical and Instrument Scope Early
- Load Lists and Demand Factors — Estimating Supply Capacity for the Unit
- Single-Line Diagram Conventions — Showing Ratings, Feeders and Protection Clearly
- Transformer and Switchboard Sizing — Choosing Ratings From the Load Schedule
- Document Numbering and Tagging Rules — Keeping Deliverables Traceable Across Disciplines

Day 2: Cables, Lighting and Small Power

- Cable Sizing for Current Rating — Applying Derating for Grouping and Ambient
- Voltage Drop and Short-Circuit Withstand Checks — Confirming Cable Selection
- Cable Schedules and Routing Layouts — Planning Trays, Trenches and Segregation
- Lighting Level Calculations — Setting Fittings for Plant Rooms and Outdoor Areas
- Small Power and Socket Outlet Layouts — Serving Maintenance and Welding Needs

Day 3: Instrument Selection and Datasheets

- Flow, Level, Pressure and Temperature Measurement Principles — Matching Sensors to Service
- Control Valve and Actuator Basics — Specifying Fail Position and Sizing Inputs
- Instrument Datasheets — Recording Process Conditions, Materials and Ranges for Vendors
- Instrument Index Structure — Linking Tags to Drawings and Datasheets
- Signal Types and Field Communication — Choosing Analogue, Discrete or Digital Signals

Day 4: Loops, Wiring and Hazardous Areas

- Loop Diagram Preparation — Tracing Signals From Field Device to Control Panel
- Junction Box and Marshalling Layouts — Allocating Terminals and Spare Capacity
- Hazardous Area Zones and Gas Groups — Defining Where Protected Equipment Is Needed
- Protection Concepts for Equipment — Selecting Flameproof, Increased Safety or Intrinsically Safe
- Earthing and Screening of Instrument Cables — Reducing Noise and Fault Risk

Day 5: Practising the Design Package

- Single-Line and Load Schedule Drafting — Applying Day 1 Methods to a Case Unit
- Cable Schedule and Lighting Layout — Applying Day 2 Calculations to the Case
- Datasheets and Loop Diagrams — Applying Day 3 and Day 4 Methods
- Interdisciplinary Checking Routine — Resolving Clashes Between Drawings, Schedules and Indexes
- Electrical and Instrumentation Design Package — Issuing the Case Unit for Review

Applying Electrical and Instrumentation Design Deliverables After the Course

- Recheck cable sizing and voltage drop on a current feeder list, recording cables that need upsizing.
- Run the checking routine on one loop set against the instrument index and junction box layouts.

Electrical and Instrumentation Design Deliverables Questions FAQ

What are electrical and instrumentation design deliverables and why do they matter now?

Electrical and instrumentation design deliverables are the drawings, schedules, calculations and datasheets that define how a plant is powered and measured. They matter now because faster projects leave less time to catch errors before procurement and construction.

Which roles gain most from electrical and instrumentation design deliverables training?

Junior electrical engineers, instrument engineers and designers gain most, especially those in engineering contractors and owner design offices. Examples come from oil and gas, water treatment and power plants.

How do electrical and instrumentation design deliverables differ from power system study courses?

Electrical and instrumentation design deliverables focus on producing the documents a contractor builds from. A power system study course analyses load flow and faults; this course covers everyday sizing, selection and drafting.

What do you bring back from electrical and instrumentation design deliverables training?

You bring back a checked design package for a case unit, with a single-line diagram, load and cable schedules, lighting layout, datasheets and loop diagrams. You also bring a reusable checking routine.

Electrical and Instrumentation Design Deliverables: The Way Forward

The electrical and instrumentation design package is the first thing to use: it informs how the next unit's drawings and schedules are prepared and checked. Designers draft from it, lead engineers review against it and document controllers issue from it. After first use, revisit the checking routine where site queries showed weak cross-checks.