JUPITER PRIME

Consulting • Training • Advisory

جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

# Pipeline Thermal Buckling Assessment Training Course

14 – 18 June 2027
Barcelona

**jupiterprime.uk**

info@jupiterprime.uk

Registered in the United Kingdom and Saudi Arabia

# Pipeline Thermal Buckling Assessment Training Course

**Ref:** 2871_109740 **Date:** 14 – 18 June 2027 **Location:** Barcelona **Fees:** 6200 GBP

Pipeline Thermal Buckling Assessment is a 1-week training course for pipeline and subsea engineers who leave with a buckling assessment and mitigation design for a hot pipeline. Hotter reservoirs, longer tiebacks and lighter seabed burial mean expansion loads now govern many layouts. Jupiter Prime Training sets Pipeline Thermal Buckling Assessment within the full design and operating life of the line.

## Why Pipeline Thermal Buckling Assessment Matters Now

Developers push production temperatures and pressures higher to reach deeper reservoirs, so the compressive effective axial force in a restrained line grows. Operators want fewer seabed interventions and less rock dumping, which shifts attention from preventing buckles to controlling where they form. Insurers and partners ask for clear evidence that a hot line will not walk into a riser or rupture at a crown. Judged well, these loads save trenching spend; misjudged, they bring fatigue cracking, local collapse or a shutdown to restrain a walking spool.

## Who Gains Most from Pipeline Thermal Buckling Assessment

- Engineers who size wall thickness and route lines across the seabed or through buried corridors
- Specialists who model soil and seabed friction and its effect on axial and lateral resistance
- Engineers who specify sleepers, distributed buoyancy and other buckle initiators
- Integrity staff who interpret survey data on buckle shape and pipeline end movement
- Project engineers who weigh trenching, rock cover and anchoring against controlled lateral buckling

Subsea design groups sending flowline, geotechnical and integrity engineers together gain most.

## Pipeline Thermal Buckling Assessment Capabilities

Participants link loads, soil response and control devices so a hot line buckles where the designer chooses.

- Calculate effective axial force profiles from temperature, pressure and end restraint — route and anchoring decisions
- Assess upheaval buckling risk for buried and trenched lines — cover height specification
- Weigh lateral buckle formation against seabed friction uncertainty — initiator spacing choices
- Design sleeper and buoyancy initiators for planned buckle sites — installation contractors
- Test pipeline walking tendency under cyclic heat-up and shutdown — riser and spool protection

- Communicate buckling margins and residual risks to project leaders — sanction and operating decisions

## Key Pipeline Thermal Buckling Assessment Terms

- Effective axial force — the net axial load from wall tension and pressure that drives a restrained line to buckle.
- Upheaval buckling — vertical movement of a buried or trenched pipeline out of its cover when compressive force exceeds the soil restraint above it.
- Lateral buckling — sideways deflection of a pipeline lying on the seabed, forming a curved lobe that releases thermal expansion.
- Buckle initiator — a feature such as a sleeper, buoyancy module or route bend that triggers a buckle at a chosen location.
- Pipeline walking — progressive axial displacement of a short line along the seabed over repeated heating and cooling cycles.
- Virtual anchor — the point along a line where friction fully restrains axial expansion, so no axial movement occurs there.

## Pipeline Thermal Buckling Assessment Day by Day

### Day 1: Thermal Expansion and Axial Load

- Temperature and Pressure Profiles — Design Case Selection for Hot Lines
- Fully Restrained Axial Force Calculation — Expected Compression at Start-Up
- Virtual Anchor and Expansion Length — End Movement at Connections
- Pipe-Soil Axial Friction Ranges — Upper and Lower Bound Choices
- Out-of-Straightness and Route Imperfections — Buckle Likelihood Along the Route

### Day 2: Upheaval Buckling of Buried Lines

- Uplift Resistance of Backfill and Rock Cover — Required Cover Height
- Trench Profile and Prop Imperfection Surveys — Critical Overbend Locations
- Uplift Mobilisation Displacement — Conservatism in Soil Parameters
- Rock Placement Versus Deeper Trenching — Intervention Cost Comparison
- Post-Lay Survey Interpretation — Remedial Cover Decisions

### Day 3: Lateral Buckling on the Seabed

- Lateral Breakout and Residual Seabed Resistance — Buckle Formation Probability
- Buckle Lobe Strain and Bending Moment — Local Collapse and Fatigue Margins
- Sleeper, Buoyancy and Snake-Lay Initiators — Planned Buckle Site Spacing
- Feed-In Length Between Buckles — Allowable Strain at Each Crown
- Finite Element Pipe-Soil Models — Validating Hand Calculations

## Day 4: Pipeline Walking and Cyclic Response

- Heat-Up and Shutdown Transients — Ratcheting Movement per Cycle
- Seabed Slope and Riser Tension Effects — Walking Direction and Rate
- Suction Pile and Anchor Restraints — Spool and Riser Protection
- Buckle Shakedown and Low-Cycle Fatigue — Operating Life Limits
- Survey Monitoring of End Expansion — Operating Envelope Updates

## Day 5: Practising the Buckling Mitigation Design

- Axial Force and Anchor Results Review — Basis for the Hot Line Case
- Cover Height and Initiator Selection — Combined Upheaval and Lateral Strategy
- Walking Restraint Sizing — End Connection Load Limits
- Peer Challenge of Soil Parameter Choices — Sensitivity and Residual Risk
- Buckling Assessment and Mitigation Design — Hot Pipeline Case Submission

## Applying Pipeline Thermal Buckling Assessment After the Course

- Rerun the effective axial force and virtual anchor check on a current flowline using upper and lower bound friction.
- Compare the latest as-laid survey of an operating line with predicted buckle sites and end expansion.

## Pipeline Thermal Buckling Assessment Questions FAQ

### What is Pipeline Thermal Buckling Assessment and why does it matter now?

Pipeline Thermal Buckling Assessment predicts how a hot, pressurised line releases expansion through upheaval, lateral buckles or walking. It matters now because higher operating temperatures and lighter seabed intervention make controlled buckling the usual design route for new flowlines.

### Which roles gain most from Pipeline Thermal Buckling Assessment?

Flowline designers, geotechnical specialists and integrity engineers gain most from Pipeline Thermal Buckling Assessment.

### How does Pipeline Thermal Buckling Assessment differ from a general pipeline engineering course?

Pipeline Thermal Buckling Assessment goes deep into one load case rather than surveying route, wall thickness and construction. You spend one week on axial force, soil response, initiators and walking, ending with a mitigation design for a single hot line.

### What do you bring back from Pipeline Thermal Buckling Assessment?

You bring back a worked buckling assessment for a hot pipeline, with chosen cover heights, initiator spacing and walking restraint. It gives your team a reusable calculation path.

## Pipeline Thermal Buckling Assessment: The Way Forward

The buckling assessment and mitigation design first informs whether a new line is trenched and covered or left on the seabed with planned buckle sites. Flowline designers, installation contractors and integrity staff all draw on it. After the first operating season, revisit the friction bounds against survey results, because measured end movement is the best guide to how conservative the original soil choices were.