JUPITER PRIME
Consulting • Training • Advisory
جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

Generator Set Alternator and Control Panel Fault-Finding Training Course

4 – 8 January 2027
Paris

Generator Set Alternator and Control Panel Fault-Finding Training Course

Ref: 3001_113738 **Date:** 4 – 8 January 2027 **Location:** Paris **Fees:** 6900 GBP

Generator Set Alternator and Control Panel Fault-Finding is a 1-week training course for electrical and maintenance technicians who keep standby and prime power generator sets ready to run, built around a generator electrical fault-finding logbook. Hospitals, data centres, plants and remote sites now lean on generator sets for longer and more often, so electrical faults left undiagnosed become outages. Jupiter Prime Training delivers Generator Set Alternator and Control Panel Fault-Finding for site maintenance crews.

Why Generator Set Alternator and Control Panel Fault-Finding Matters Now

Critical loads such as data halls and operating theatres expect a set to start, regulate and accept load within seconds. Digital controllers have replaced relay panels, so faults hide in parameters and alarm logs rather than burnt contacts. Sets increasingly run in parallel with each other or with the network, adding synchronising and load sharing faults. Diagnosing from measurements restores supply quickly; guessing repeats failures at the worst moment. The course rests on insulation testing practice, excitation and governor control principles, and structured fault-finding logic.

Who Gains Most from Generator Set Alternator and Control Panel Fault-Finding

- Technicians responsible for routine electrical checks on standby generator sets
- Crews running prime power sets at remote camps, mines and island networks
- Maintainers of synchronising panels and parallel generator switchboards
- Staff who carry out load bank tests and record set performance
- Electricians who respond to generator alarms and failed transfers

Facility maintenance crews who share a fleet of sets gain most when several members attend, because they leave with one common fault-finding sequence.

Generator Set Alternator and Control Panel Capabilities

Outcomes run from winding measurements to load sharing controls.

- Test stator and rotor winding insulation and continuity — repair or rewind decisions
- Diagnose excitation and voltage regulator faults from field measurements — restoring stable output voltage
- Assess governor response and speed droop settings — frequency stability for critical loads
- Apply synchronising checks to phase sequence, voltage and frequency match — safe paralleling
- Calculate active and reactive load sharing between parallel sets — avoiding reverse power trips
- Build load bank test records — maintenance planners and facility managers

Key Generator Set Alternator and Control Panel Terms

- Brushless exciter — a small alternator on the main shaft whose output, rectified by rotating diodes, feeds the main field winding.
- Voltage regulator — the controller that adjusts exciter field current to hold alternator output voltage steady as load changes.
- Speed droop — the planned fall in engine speed as load rises, letting parallel sets share active load in proportion.
- Reverse power — power flowing into a generator so it motors, a condition protection trips to protect the engine.
- Polarisation index — the ratio of insulation resistance readings taken at two times, showing moisture or contamination in windings.
- Load bank — a controlled resistive or reactive load used to test a set at rated output without site load.

Generator Set Alternator and Control Panel Day by Day

Day 1: Generator Set Duties and Electrical Layout

- Standby, Prime And Continuous Ratings — Matching Set Duty To Site Load
- Alternator Construction, Windings And Terminal Markings — Reading The Machine
- Control Panel Layout, Sensors And Alarm Logs — Locating Fault Evidence
- Automatic Transfer Switch Sequence — Mains Failure And Return Timing
- Safe Isolation Of Generator Sets — Preventing Unexpected Start Or Backfeed

Day 2: Windings, Insulation and Rotating Diodes

- Insulation Resistance And Polarisation Index Tests — Winding Condition Judgement
- Winding Resistance And Continuity Checks — Shorted Turns And Open Circuits
- Rotating Diode And Surge Suppressor Testing — Exciter Rectifier Failures
- Bearing, Alignment And Vibration Symptoms — Separating Electrical From Mechanical Causes
- Drying Out Damp Windings — Return To Service Decisions

Day 3: Excitation, Voltage and Speed Control

- Exciter Field Measurements And Residual Magnetism — No Voltage Build-Up Faults
- Voltage Regulator Setting, Stability And Sensing — Hunting And Overvoltage Faults
- Electronic Governor Gain, Droop And Isochronous Modes — Frequency Recovery
- Step Load Response Testing — Critical Load Acceptance
- Controller Parameter Backup And Comparison — Tracing Configuration Errors

Day 4: Paralleling, Load Sharing and Protection

- Synchroscope, Check Synchronising Relay And Breaker Closing — Safe Paralleling
- Active And Reactive Load Sharing Lines — Circulating Current Faults
- Generator Protection Functions And Trip Records — Overcurrent, Reverse Power, Loss Of Excitation
- Earthing Arrangements For Single And Parallel Sets — Neutral Current And Fault Clearance
- Mains Parallel Operation And Soft Transfer — Network Interface Settings

Day 5: Practising Generator Fault-Finding

- Structured Fault-Finding Sequence On Alarm Scenarios — Half-Split Diagnosis
- Insulation And Diode Test Case Review — Repair Recommendation
- Governor And Regulator Tuning Case — Load Acceptance Improvement
- Load Bank Test Plan And Result Interpretation — Rated Output Confirmation
- Generator Electrical Fault-Finding Logbook — Handover To Site Maintenance

Applying Generator Set Alternator and Control Panel Fault-Finding After the Course

- Run insulation resistance and polarisation index tests on site sets and record trends for each alternator.
- Lead a load bank test with step loads, logging voltage and frequency recovery against regulator and governor settings.

Generator Set Alternator and Control Panel Fault-Finding Questions FAQ

What is generator set alternator and control panel fault-finding, and why does it matter now?

It is the diagnosis of faults on the electrical side of a generator set: windings, excitation, regulation, governing, synchronising and protection. It matters now because critical loads depend on sets that start and accept load reliably.

Which roles gain most from generator set alternator and control panel fault-finding training?

Electrical and maintenance technicians who test, run and repair standby or prime power sets gain most, including those who maintain synchronising panels.

How does generator set alternator and control panel fault-finding differ from diesel engine maintenance training?

It stays on the electrical machine and its controls. Engine courses cover fuel, cooling and lubrication; this subject covers windings, exciters, regulators, governors, paralleling and protection faults.

What do you bring back from generator set alternator and control panel fault-finding training?

You bring back a fault-finding logbook of test methods, expected readings and diagnosis sequences for your site sets.

Generator Set Alternator and Control Panel Fault-Finding: The Way Forward

The generator electrical fault-finding logbook first informs whether a failed set needs a part, a setting change or a rewind. Maintenance technicians and supervisors use it on every alarm and test. After its first use, revisit the expected readings for each set, since insulation and response figures drift with age, climate and duty.