JUPITER PRIME

Consulting • Training • Advisory

جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

Electrical Equipment Lifecycle Performance Training Course

22 – 26 November 2027
Milan

jupiterprime.uk

info@jupiterprime.uk

Registered in the United Kingdom and Saudi Arabia

Electrical Equipment Lifecycle Performance Training Course

Ref: 3100_117722 **Date:** 22 – 26 November 2027 **Location:** Milan **Fees:** 7200 GBP

Electrical Equipment Lifecycle Performance Training Course is a 1-week training course for electrical engineers, equipment specialists and reliability staff who build an equipment lifecycle assurance plan for transformers, switchgear, motors and cables. Unplanned outages, ageing installed fleets and tighter capital budgets now push organisations to judge equipment on decades of service rather than purchase price alone. This course on electrical equipment lifecycle performance is delivered by Jupiter Prime Training.

Why Electrical Equipment Lifecycle Performance Matters Now

Three forces shape this subject today. Installed fleets of transformers, switchgear and cables are ageing. Slimmer design margins mean weak specifications surface later as site failures. Finance teams and asset owners expect every replacement to be justified with evidence. An organisation that controls equipment from specification through testing to monitoring avoids sudden outages, repeat failures and rushed replacements. The course rests on recognised international practice for equipment testing, insulation coordination and condition assessment, described in general terms.

Who Gains Most from Electrical Equipment Lifecycle Performance

- Engineers who write and review technical specifications for electrical plant purchases
- Specialists who witness factory tests and sign off site acceptance results
- Reliability staff who run monitoring routes and interpret condition trends
- Maintenance engineers who decide on repair, refurbishment or replacement of ageing equipment

Utility, industrial and facility engineering groups gain most when purchasing, testing and maintenance staff attend together and agree one shared record for each asset.

Electrical Equipment Lifecycle Performance Capabilities

Participants connect specification wording to site measurements and long-term condition trends.

- Assess specification clauses for ratings, margins and thermal limits — purchase approvals
- Specify factory witness and site acceptance tests with clear pass criteria — energisation readiness
- Apply oil, discharge, thermal and motor condition techniques — outage scheduling
- Calculate an equipment health index from test and monitoring results — capital spend ranking
- Build a failure investigation timeline that feeds lessons back to buyers — repeat failure prevention
-

Weigh refurbishment, retrofit and replacement options on lifecycle cost — asset owners and finance

Key Electrical Equipment Lifecycle Performance Terms

- Lifecycle cost — the total cost of buying, installing, operating, maintaining and finally disposing of equipment over its service life.
- Factory witness test — a test at the manufacturer's works, observed by the buyer, to confirm equipment meets its specification before delivery.
- Site acceptance test — checks made after installation to confirm equipment arrived undamaged and was installed correctly, recording baseline values for later comparison.
- Dissolved gas trending — tracking gases formed in transformer oil over time to reveal overheating, arcing or insulation breakdown inside the tank.
- Partial discharge — small electrical sparks within insulation that do not bridge the conductors but steadily erode insulation until failure.
- Health index — a single score combining test, monitoring and age data that ranks equipment by condition and urgency of action.

Electrical Equipment Lifecycle Performance Day by Day

Day 1: Lifecycle Forces and Failure Patterns

- Equipment Lifecycle Stage Mapping — Where Reliability Is Won or Lost
- Failure Mode Patterns in Transformers and Switchgear — Inspection Priorities
- Motor and Cable Ageing Mechanisms — Expected Service Life Assumptions
- Duty Cycle and Loading Profiles — Matching Equipment to Real Service
- Lifecycle Cost Comparison — Purchase Price Versus Total Ownership Cost

Day 2: Specification Review and Purchase Decisions

- Technical Specification Clause Review — Gaps That Cause Early Failures
- Ratings, Margins and Derating Factors — Sizing for Site Conditions
- Insulation Class and Temperature Rise Limits — Thermal Headroom Choices
- Tender Technical Comparison Matrix — Choosing Between Competing Offers
- Manufacturer Design Review Meetings — Agreeing Drawings Before Manufacture

Day 3: Factory and Site Testing

- Factory Witness Test Plans — Which Routine and Type Tests to Attend
- Insulation Resistance and Dielectric Withstand Tests — Accept or Reject
- Winding Resistance and Turns Ratio Checks — Transformer Acceptance Evidence
- Site Acceptance Test Records — Baseline Values for Later Trending
- Punch List and Defect Closure Logs — Readiness for Energisation

Day 4: Condition Monitoring in Service

- Dissolved Gas Trending in Transformer Oil — Intervention Timing
- Partial Discharge Surveys on Switchgear and Cables — Repair Priorities
- Thermal Imaging Routes and Hot Spot Grading — Outage Scheduling
- Motor Current Signature and Vibration Checks — Rewind or Replace
- Equipment Health Index Scoring — Ranking Assets for Capital Spend

Day 5: Practising the Equipment Lifecycle Assurance Plan

- Failure Investigation and Root Cause Timelines — Lessons Fed Back to Buyers
- Specification Lessons Register — Updating Purchase Clauses From Failures
- Test Baseline and Monitoring Interval Alignment — One Asset Record
- Refurbish, Retrofit or Replace Decision Matrix — End of Life Timing
- Equipment Lifecycle Assurance Plan — Assembling the Final Work Product

Applying Electrical Equipment Lifecycle Performance After the Course

- Lead a specification lessons review that compares recent site failures with the purchase clauses of the affected transformers, switchgear or motors.
- Set up a health index score for one group of critical assets using existing acceptance baselines and monitoring results.

Electrical Equipment Lifecycle Performance Questions FAQ

What is electrical equipment lifecycle performance and why does it matter now?

Electrical Equipment Lifecycle Performance is the practice of controlling equipment from specification through testing and monitoring to replacement. It matters now because ageing fleets, slimmer design margins and tight budgets make failures costlier.

Which roles gain most from electrical equipment lifecycle performance training?

Specification engineers, test witnesses, reliability analysts and maintenance engineers gain most from electrical equipment lifecycle performance training.

How does electrical equipment lifecycle performance differ from a single equipment maintenance course?

Electrical Equipment Lifecycle Performance links every stage of equipment life rather than one task. A maintenance course on one equipment type teaches repair steps, while this subject connects specification choices, test baselines and monitoring trends across transformers, switchgear, motors and cables.

What do you bring back from electrical equipment lifecycle performance training?

You bring back a structured assurance plan from electrical equipment lifecycle performance training. It ties specification lessons, test baselines and monitoring intervals together for your own critical assets.

Electrical Equipment Lifecycle Performance: The Way Forward

The equipment lifecycle assurance plan first informs which critical transformers, switchgear panels, motors or cable circuits need action in the next outage window. Purchasing engineers, maintenance planners and asset owners each use it to align specifications, test baselines and monitoring routes. After its first use, revisit the health index weightings against actual failures, so scoring reflects real service.