JUPITER PRIME

Consulting • Training • Advisory

جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

Advanced GNSS Control Network Survey and Quality Control Training Course

14 – 25 June 2027
Munich

jupiterprime.uk

info@jupiterprime.uk

Registered in the United Kingdom and Saudi Arabia

Advanced GNSS Control Network Survey and Quality Control Training Course

Ref: 817_31071 **Date:** 14 – 25 June 2027 **Location:** Munich **Fees:** 11100 GBP

GNSS control network survey and quality control is a 2-week advanced training course for surveyors and geomatics engineers who design, observe and adjust GNSS control, and it produces a control network survey and QC report. Infrastructure, mapping and construction projects now depend on control marks whose coordinates and uncertainties can be defended long after the field crew has left. Jupiter Prime Training builds this course around field evidence and adjustment statistics.

Why GNSS Control Network Survey and Quality Control Matters Now

Three forces shape GNSS control work today. Multi-constellation receivers and correction services have made observation faster, which tempts crews to skip redundancy. Clients in rail, utilities and land administration now ask for documented uncertainty rather than a coordinate list. And control marks are reused by machine guidance, laser scanning and drone photogrammetry, so a weak mark spreads error into every later product. A network that is designed for redundancy and tested statistically protects design decisions, settlement claims and setting-out; a network that is not exposes the project to rework and disputes over position.

Who Gains Most from GNSS Control Network Survey and Quality Control

- Specialists who plan control layouts, station spacing and observation sessions for project or regional networks
- Field leads responsible for static and RTK occupations, antenna heights and logging records
- Processing analysts who resolve baselines, choose ephemerides and screen ambiguities
- Adjustment specialists who run constrained and minimally constrained least squares solutions
- Survey checkers who sign off control before it is released to design or construction teams

Survey departments that send a planner, a field lead and a processing analyst together gain most, because each sees how the others create or remove error.

GNSS Control Network Survey and Quality Control Capabilities

Participants leave able to carry a control network from station layout to a signed statistical report.

- Design network geometry with independent baselines and redundancy — station layout approval
- Specify static session lengths and RTK check procedures — field crew briefings
- Assess baseline solutions using ratio, RMS and fixed ambiguity results — rejection or reobservation
- Calculate minimally constrained and fully constrained adjustments — datum and fixed station choices
- Test residuals with the chi-square global test and standardised residual screening — outlier decisions
- Communicate error ellipses and relative precision to project engineers — control release sign-off

Key GNSS Control Network Survey and Quality Control Terms

- Independent baseline — a vector between two receivers that is not derived from other vectors in the same session, used to avoid false redundancy.
- Minimally constrained adjustment — a least squares solution holding only one station fixed, revealing internal network consistency before external control is applied.
- Integer ambiguity — the whole number of carrier wavelengths between satellite and antenna that must be resolved for precise baseline results.
- Standardised residual — an observation residual divided by its standard deviation, used to flag possible blunders in an adjustment.
- Error ellipse — the plotted horizontal uncertainty of an adjusted station at a stated confidence level.
- Loop closure — the misclosure found when baseline vectors around a closed figure are summed, indicating field or processing errors.

GNSS Control Network Survey and Quality Control Day by Day

Day 1: Control Purpose and Accuracy Classes

- Project Accuracy Specifications — Choosing Network Order and Tolerance
- Reference Frames and Epochs — Aligning Coordinates with Existing Control
- Geoid Models and Orthometric Heights — Deciding Height Derivation Strategy
- Error Budgets for GNSS Positions — Allocating Tolerance Across Field and Office
- Client Deliverable Requirements — Defining Reports, Schedules and Mark Records

Day 2: Network Design and Station Layout

- Station Reconnaissance and Sky Plots — Rejecting Sites with Multipath or Obstruction
- Network Geometry and Redundancy — Planning Independent Baselines Per Session
- Pre-Analysis of Expected Precision — Testing Layout Before Field Mobilisation
- Monument Types and Mark Stability — Selecting Marks for Long Reuse
- Session Scheduling with Satellite Availability — Assigning Receivers and Occupation Times

Day 3: Static Observation Practice

- Antenna Height Measurement and Phase Centre Models — Reducing Vertical Bias
- Logging Rates and Elevation Masks — Balancing Data Volume and Quality
- Field Booking Sheets and Photographs — Proving Occupation Conditions
- Multi-Constellation Tracking Choices — Improving Geometry Under Partial Sky View
- Repeat Occupations on Separate Days — Detecting Setup and Centring Errors

Day 4: RTK and Network RTK Methods

- Single Base RTK Configuration — Limiting Baseline Length for Control Use
- Network RTK Correction Services — Judging Suitability for Lower-Order Control
- Initialisation Checks and Re-Fix Procedures — Confirming Ambiguity Integrity
- Check Shots on Known Marks — Validating Each RTK Session
- RTK Versus Static Selection Matrix — Matching Method to Network Order

Day 5: Baseline Processing

- Broadcast and Precise Ephemerides — Choosing Orbit Products for Processing
- Ionosphere-Free and Wide-Lane Solutions — Handling Long Baselines
- Ratio and Reference Variance Indicators — Accepting or Rejecting Fixed Solutions
- Cycle Slip and Multipath Screening — Editing Satellites and Time Spans
- Processing Logs and Version Control — Making Baseline Results Repeatable

Day 6: Pre-Adjustment Checks

- Loop Closures and Repeat Baseline Comparison — Isolating Suspect Vectors
- Trivial Baseline Removal — Preventing Inflated Redundancy
- Station Identifier and Height Audits — Catching Booking Blunders
- Variance Scaling of Baseline Vectors — Realistic Weighting Before Adjustment
- Network Connectivity Diagrams — Confirming Every Station Is Tied

Day 7: Least Squares Adjustment

- Observation Equations and Weight Matrices — Building the Functional Model
- Minimally Constrained Solution — Revealing Internal Network Consistency
- Constrained Solution to Existing Control — Selecting Fixed Stations
- Free Network and Inner Constraints — Assessing Datum Defects
- Height Adjustment with Geoid Separation — Producing Orthometric Results

Day 8: Statistical Quality Control Tests

- Chi-Square Global Test — Judging Overall Model Validity
- Standardised Residuals and Data Snooping — Flagging Outlying Observations
- Internal and External Reliability — Measuring Undetected Blunder Size
- Error Ellipses and Relative Precision — Comparing Results with Specification
- Control Station Movement Tests — Deciding Whether Fixed Marks Have Shifted

Day 9: Sector Cases and Reporting Standards

- Rail Corridor Control Case — Densifying Along Narrow Linear Networks
- Utility and Pipeline Control Case — Tying Remote Stations to Primary Marks
- Coordinate Schedules and Station Descriptions — Structuring Deliverables for Reuse
- Metadata and Transformation Parameters — Recording Frame, Epoch and Geoid
- Peer Checking Procedures — Assigning Independent Review Before Release

Day 10: Practising the Control Network Survey and QC Report

- Network Design Review from Station Layout — Confirming Redundancy and Geometry
- Baseline Processing Audit Trail — Linking Field Records to Results
- Adjustment Statistics Interpretation — Defending Accepted and Rejected Observations
- Uncertainty Statement Drafting — Explaining Precision to Project Engineers
- Control Network Survey and QC Report Assembly — Release for Design Use

Applying GNSS Control Network Survey and Quality Control After the Course

- Rerun the adjustment of a recent control job with a minimally constrained solution and residual screening, then record which baselines would now be reobserved.
- Introduce a pre-analysis and session schedule template for the next network, checked against the project accuracy class before mobilisation.

GNSS Control Network Survey and Quality Control Questions FAQ

What is GNSS control network survey and quality control, and why does it matter now?

It is the design, observation, adjustment and statistical testing of GNSS control marks. It matters now because scanning, drones and machine guidance all inherit the accuracy of the control beneath them, and clients expect documented uncertainty rather than bare coordinates.

Which roles gain most from GNSS control network survey and quality control?

Network planners, field leads, processing analysts and survey checkers gain most. You benefit if you approve station layouts, run static or RTK sessions, resolve baselines or sign off adjusted coordinates before they reach design teams.

How does GNSS control network survey and quality control differ from a general GNSS surveying course?

It concentrates on control rather than detail capture. A general GNSS course covers receiver operation and topographic pickup, while this course centres on redundancy, least squares adjustment and statistical tests that prove a network meets its accuracy class.

What do you bring back from GNSS control network survey and quality control?

You bring back a control network survey and QC report built on a realistic network. It links station design, baseline processing records, adjustment statistics and uncertainty statements in a form your checker and your client can follow.

GNSS Control Network Survey and Quality Control: The Way Forward

The control network survey and QC report first informs whether adjusted coordinates can be released for design and setting-out. Project engineers, checkers and later survey crews rely on it when they occupy the same marks. After its first use, revisit the weighting and fixed station choices, since mark stability and frame updates change what a sound constraint looks like over time.