JUPITER PRIME

Consulting • Training • Advisory

جوبيتر برايم للاستشارات والتدريب

COURSE BROCHURE

# Electrical Systems Pre-Commissioning and Energisation Training Course

4 – 8 January 2027
Casablanca

**jupiterprime.uk**

info@jupiterprime.uk

Registered in the United Kingdom and Saudi Arabia

# Electrical Systems Pre-Commissioning and Energisation Training Course

**Ref:** 2600_98882 **Date:** 4 – 8 January 2027 **Location:** Casablanca **Fees:** 4900 GBP

Electrical Systems Pre-Commissioning and Energisation is a 1-week training course for commissioning engineers and technicians who bring switchboards, transformers and motors into service, and each participant builds an energisation readiness dossier. Utilities, commercial buildings and industrial plants now connect more equipment under tighter handover windows, so a missed test or an unclear switching step turns directly into damaged plant or lost supply. Jupiter Prime Training delivers this Electrical Systems Pre-Commissioning and Energisation course.

## Why Electrical Systems Pre-Commissioning and Energisation Matters Now

Three pressures shape this work today. Asset owners expect faster handover from construction contractors, compressing the time between final termination and first energisation. Operations teams inherit mixed vendor equipment with patchy test records. Insurers and safety committees ask for evidence that every circuit was proven before voltage was applied. Good sequencing hands over documented equipment; poor sequencing brings insulation failures, protection maloperation and defect disputes. The course rests on manufacturer test sheets, recognised international testing practice for low and medium voltage equipment, and the site's own switching and permit rules.

## Who Gains Most from Electrical Systems Pre-Commissioning and Energisation

- Engineers who plan test sequences and sign off circuits before first voltage
- Technicians who perform insulation, continuity and secondary injection tests on site
- Supervisors who coordinate contractors, vendors and operations during switchover
- Maintenance staff who take ownership of new switchboards, transformers and drives
- Site representatives who verify test records against drawings at handover

A substation, building services or plant electrical crew gains most when its test, supervision and operations members attend together and agree one sequence for proving and switching new equipment.

## Electrical Systems Pre-Commissioning and Energisation Capabilities

Participants move from loose test sheets to a controlled path from termination to live service.

- Specify pre-commissioning checks for switchboards, transformers and motors — the contractor's inspection and test plan
- Apply insulation resistance and polarisation index tests correctly — the decision to accept or dry out a winding
- Test protection relays through secondary and primary injection — the protection engineer's setting acceptance
- Design a stepwise energisation sequence with hold points — the operations controller's switching approval
- Build and close a categorised punch list — the owner's handover decision
- Communicate readiness evidence to permit and safety authorities on site — the first-voltage authorisation

## Key Electrical Systems Pre-Commissioning and Energisation Terms

- Pre-commissioning — de-energised checks confirming equipment is installed, terminated and safe before voltage is applied.
- Insulation resistance test — a direct-voltage test measuring leakage to reveal moisture or damage in cables and windings.
- Polarisation index — the ratio of two timed insulation readings, indicating winding dryness.
- Secondary injection — applying test signals to a relay's inputs to prove its settings and trip outputs.
- Energisation — the controlled first application of rated voltage, following a sequence with hold points.
- Punch list — a register of open defects, graded by whether they block energisation or handover.

## Electrical Systems Pre-Commissioning and Energisation Day by Day

### Day 1: Scope, Boundaries and Safe Systems

- System Boundary Drawings — Deciding Where Each Test Package Starts and Ends
- Inspection and Test Plans — Assigning Witness and Hold Points to Parties
- Permit-to-Work and Lock-Out Rules — Controlling Access During Testing
- Single-Line Diagram Verification — Confirming Installed Equipment Matches Design
- Vendor Test Certificates — Judging Which Factory Results Need Site Repetition

### Day 2: Switchboard and Cable Checks

- Busbar Torque and Visual Inspection — Accepting Mechanical Completion of Panels
- Cable Insulation Resistance Testing — Accepting or Rejecting Installed Feeders
- Continuity and Phasing Checks — Preventing Crossed Phases at First Closure
- Circuit Breaker Timing and Contact Resistance — Proving Switching Device Health
- Earthing System Resistance Measurement — Confirming Fault Return Paths Are Sound

## Day 3: Transformers, Motors and Protection

- Transformer Ratio and Vector Group Tests — Confirming Correct Winding Connections
- Winding Polarisation Index Readings — Deciding Whether Drying Out Is Needed
- Motor Rotation and Uncoupled Runs — Releasing Drives for Coupled Operation
- Relay Secondary Injection — Accepting Protection Settings and Trip Logic
- Current Transformer Polarity and Loop Checks — Ensuring Protection Sees Real Faults

## Day 4: Energisation Sequencing

- Switching Schedule Drafting — Ordering Each Closure With Hold Points
- Soak Period Monitoring — Detecting Early Faults Under Rated Voltage
- First Load Checks and Thermal Imaging — Confirming Connections Under Current
- Abort Criteria and Back-Out Steps — Deciding When to De-Energise Safely
- Utility and Building Interface Coordination — Aligning Outages With Other Parties

## Day 5: Practising the Energisation Readiness Dossier

- Punch List Categorisation — Separating Energisation Blockers From Handover Items
- Test Record Reconciliation Against the Inspection Plan — Closing Evidence Gaps
- Mock Switching Walk-Through on a Case Substation — Testing the Sequence
- Handover Sign-Off Matrix — Assigning Acceptance to Owner and Contractor
- Energisation Readiness Dossier Assembly — Presenting the First-Voltage Case

## Applying Electrical Systems Pre-Commissioning and Energisation After the Course

- Lead a review of an upcoming switchboard or transformer package against the checks and hold points covered.
- Run a punch list categorisation session with the contractor before the next switching date.

## Electrical Systems Pre-Commissioning and Energisation Questions FAQ

### What is electrical systems pre-commissioning and energisation, and why does it matter now?

It is the controlled testing of de-energised equipment followed by its first switching to rated voltage. Shorter handover windows raise the chance that an untested fault meets live voltage.

### Which roles gain most from electrical systems pre-commissioning and energisation training?

Commissioning engineers and test technicians gain most, along with supervisors who coordinate switching and maintenance staff who take over new plant.

## How does electrical systems pre-commissioning and energisation training differ from a facility startup course?

It concentrates on electrical equipment alone across utilities, buildings and industry. Whole-facility startup courses cover process systems and control loops; this one goes deeper into insulation, protection and switching.

## What do you bring back from electrical systems pre-commissioning and energisation training?

You bring back a structured readiness case for one real package. It combines test records, a categorised punch list, a switching sequence and a sign-off matrix.

## Electrical Systems Pre-Commissioning and Energisation: The Way Forward

The energisation readiness dossier first informs the go or no-go decision for applying voltage to a new switchboard, transformer or motor circuit. Commissioning leads, operations controllers and asset owners use it to agree what is proven and what remains open. After its first use, revisit how factory and site test results are reconciled, since that is where gaps most often hide.